(*f*) The Range Officer at the beginning of each period mentioned in clause (a) will inform, in writing, the contractor the quantity of timber available for carting.

(*g*) The contractor shall abide by the rules of the Department as regards kindling of fires and hold himself responsible for any offence committed by him or his agents, employees or cartmen.

(*h*) The security furnished will be returned to the contractor three months after the expiry of the contract period if the whole or any portion of it is not forfeited to Government by the violation of the terms of the contract and after the District Forest Officer has satisfied himself that no timber is outstanding against the contractor.

(*i*) Payments will be made by cheques once in every month on the bills complied by the Range Officer concerned. Rules regarding the elimination of pies and annas will be observed as per standing orders.

K. REVANNA,
*District Forest Officer.*

## ENGINEERING DEPARTMENT

### BANGALORE DIVISION.

*Notification dated 5th August* 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 26th August 1935, for Restoring Chickonahally Kamanahally Kodagikere Minor Tank Register No. 245 of Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred only (Rs. 300) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Chikonahally Kamanahally Kodagikere Minor Tank, Register No. 245 of Hoskote Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for restoring Chickonahally Kamanahally Kodagikere Minor Tank Registered No. 245 of Hoskote Taluk.

| | Items of work | Unit | Quantity | Rate in Figures | Rate in Words |
|---|---|---|---|---|---|
| | **BUND.** | | | | |
| 1. | Clearing Lantana Jungle .. .. .. | Grade | 21 | | |
| 2. | Cutting grips and toe trenches .. .. | ,, | 24 | | |
| 3. | Earthwork to bund including watering and tamping .. .. .. .. .. | C.yd. | 11,875 | | |
| 4. | Turfing to slopes of bund and watering till it grows .. .. .. .. .. | S.yd. | 8,123 | | |
| 5. | New stone revetment .. .. .. | C.yd. | 937 | | |
| 6. | Removing and resetting old stone work with new jelly .. .. .. .. .. | ,, | 105 | | |
| 7. | Providing and fixing new grade stones with bed slabs, figures chiselled and painted | Each | 27 | | |
| 8. | Do Registered and Date Stones do | ,, | 1 | | |
| 9. | Do B. M. stones do | ,, | 2 | | |
| 10. | Do Gauge stones do | ,, | 1 | | |
| 11. | Do Index stones do | ,, | 27 | | |
| | **SLUICE.** | | | | |
| 1. | Earthwork cut opening the bund .. .. | C.yd. | 60 | | |
| 2. | Removing and resetting old stone revetment with new jelly .. .. .. .. | ,, | 7 | | |
| 3. | Stone jelly concrete in surki mortar .. .. | C.ft. | 106 | | |
| 4. | Burnt brick in surki mortar .. .. .. | ,, | 193 | | |
| 5. | Plastering with surki mortar .. .. | Sqr. | 2·10 | | |
| 6. | Burnt stone slabs 6″ thick dressed and fixed in surki mortar .. .. .. .. | S.ft. | 66 | | |
| 7. | Cutting orifices in slabs .. .. .. | Each | 4 | | |
| 8. | Fixing cast iron pipes 6″ Dia. including conveying from divisional office, etc., complete pipes supplied departmentally .. .. .. | R.ft. | 27 | | |
| 9. | Refilling the earth got from cut opening the bund and consolidation .. .. .. .. | C.yd. | 60 | | |
| 10. | Providing and fixing wooden plug with Locking arrangements, etc., complete .. .. | Each | 1 | | |
| 11. | Rough stone work, new .. .. .. | C.yd. | 3 | | |
| | **WASTE WEIR** | | | | |
| 1. | Earthwork excavation, forming bank with consolidation .. .. .. .. | C.yd. | 87 | | |
| 2. | Burnt brick in surki mortar .. .. .. | C.ft. | 226 | | |
| 3. | Burnt stone slabs 6″ thick dressed and fixed in surki mortar .. .. .. .. | S.ft. | 111 | | |
| 4. | Joggle Joints .. .. .. .. | Each | 10 | | |
| 5. | Plastering with surki mortar .. .. | Sqr. | 3·37 | | |
| 6. | Rough stone work, new .. .. .. | C.yd. | 25 | | |

M. A. SRINIVASACHARI,
*Executive Engineer.*